Floor Grading:- Immediately after the backfilling around the walls, columns, etc. has been completed, grade the entire floor area of the building to within 6" of the finished floor levels, using material now on the site; the fill to be thoroughly tamped and wetted as it is being put down and left free from soft pits and holes.

The filling material to be clean, free from rocks, stones, rubbish and foreigh material. The intent being that the fill will form a firm support for the concrete floor, which will not settle or permit settlement.

Service Systems:- Service system contractors will do their own excavating and backfill all excavations so there will be no subsequent settlement.

Anchors and Miscellaneous Iron Work:- The contractor is to set and anchor all miscellaneous iron workerequired in concrete masonry.

Pipe and Other Openings:- Contractor is to provide pipe and other openings in foundations and other walls and floors, where specified, indicated or directed.

Protection of Conduit, Pipe, etc.:- The contractor to use extreme care not to move or dislocate any conduit, piping, hangers, or other systems installed in the floors.

Cement:- Portland Cement to be a well recognized brand to meet City specifications and requirements of the A.S.T.M.